



# Advanced Virgo Status

Matteo Barsuglia (Astroparticule et Cosmologie – CNRS)  
On behalf of the Virgo Collaboration



# Advanced Virgo

- Advanced Virgo (AdV): upgrade of the Virgo interferometric detector of gravitational waves
- Participated by scientists from Italy and France (former founders of Virgo), The Netherlands, Poland and Hungary
- Funding approved in Dec 2009 (23.8 ME)
- Construction in progress. End of installation: fall 2015
- First science data in 2016

5 European countries  
19 labs, ~200 authors

APC Paris  
ARTEMIS Nice  
EGO Cascina  
INFN Firenze-Urbino  
INFN Genova  
INFN Napoli  
INFN Perugia  
INFN Pisa  
INFN Roma La Sapienza  
INFN Roma Tor Vergata  
INFN Trento-Padova  
LAL Orsay – ESPCI Paris  
LAPP Annecy  
LKB Paris  
LMA Lyon  
NIKHEF Amsterdam  
POLGRAW (Poland)  
RADOUD Uni. Nijmegen  
RMKI Budapest








# Advanced Virgo




# Sensitivities





# Noise budget

gravity  
gradient  
noise




Coating thermal  
noise

Quantum noise

# Optical scheme

- Dual recycled Fabry-Perot Michelson
- Bi-concave arm-cavities
- Marginally stable recycling cavities
- Compensation plates
- Pick-off plate for ITF control

Advanced Virgo main Optical parameters			
<b>Light Power</b>			
arm cavity power	650 kW	power on BS	4.9 kW
<b>Arm cavity geometry</b>			
cavity length $L$	2999.8 m		
IM $R_C$	1420 m	EM $R_C$	1683 m
Beam size on IM $w$	48.7 mm	Beam size on EM $w$	58.0 mm
waist size $w_0$	9.69 mm	waist position $z$	1363 m
<b>Arm cavity finesse</b>			
finesse	443	round-trip losses	75 ppm
transmission IM $T$	1.4%	transmission EM $T$	1 ppm
<b>Power recycling</b>			
transmission PRM $T$	5%	recycling gain	37.5
PRC length	11.952 m	Beam size on PRM	49.1 (TBC) mm
<b>Signal recycling</b>			
transmission SRM $T$	20%	finesse	26
SRC length	11.952 m	SRM tuning	0.35 rad
<b>Mirrors</b>			
IM diameter	35 cm	EM diameter	35 cm
IM thickness	20 cm	EM thickness	20 cm








# Some of the changes with respect to Virgo

- Larger beam (thermal noise)
- Higher quality optics (thermal noise, quantum noise)
- Heavier mirrors (thermal noise, quantum noise)
- 200W fiber laser
- thermal control of aberrations
- signal recycling
- Improvement in the suspension lower stage
- Suspended and under vacuum auxiliary benches
- Baffles




# Coating thermal noise

$$x^2(\omega) = \frac{4k_B T}{\omega} \frac{1 - \sigma^2}{\pi E_0} \frac{d}{\omega^2} \left( \frac{E_0}{E_{\perp}} \phi_{\perp}(\omega) + \frac{E_{\parallel}}{E_0} \phi_{\parallel}(\omega) \right)$$

coating thickness  $d$   
 beam radius  $\omega$   
 Young modulus substrate  $E_0$   
 Young modulus coating  $E_{\perp}, E_{\parallel}$   
 loss angle coating  $\phi_{\perp}(\omega), \phi_{\parallel}(\omega)$

$x \sim \frac{1}{\omega^2}$      $x \sim \sqrt{\pi}$      $x \sim \sqrt{d}$      $x \sim \sqrt{\phi}$


21 mm  $\rightarrow$  49 mm







Power recycling

Beam splitter








First coating on a large optics: CP




# First map of test masses



**PRELIMINARY**

Flatness: 0.17 nm rms on 150mm  $\phi$   
(spec.: 0.5 nm rms)


RoC: 1425 m (spec.: 1420 [-5,+15] m)





# Some of the changes with respect to Virgo

- Larger beams
- Higher quality optics
- Heavier mirrors
- 200W fiber laser (quantum noise)
- thermal control of aberrations (quantum noise)
- signal recycling (quantum noise)
- Improvement in the suspension lower stage
- Suspended and under vacuum auxiliary benches
- Baffles







# 2015 configuration


- Start in 2015 with a simplified configuration: likely to reduce commissioning time
  - No signal recycling (reduce locking complexity)
  - Virgo+ laser (up to 60W)
  - Low power (reduce risks with thermal effects and high power laser)
- Target BNS inspiral range:  $>100$  Mpc







# Some of the changes with respect to Virgo

- Larger beam
- Higher quality optics
- Heavier mirrors
- thermal control of aberrations
- *200W fiber laser*
- *signal recycling*
- *Improvement in the suspension lower stage (thermal noise, suspend CP/ baffles)*
- Suspended and under vacuum auxiliary benches
- Baffles







BS payload installation in July 2014



First test mass Dec 2014








# Some of the changes with respect to Virgo


- Larger beam
- Higher quality optics
- Heavier mirrors
- thermal control of aberrations
- *200W fiber laser*
- *signal recycling*
- *Improvement in the suspension lower stage*
- *Suspended and under vacuum auxiliary benches (backscattering)*
- *Baffles (backscattering)*






# Backscattering



- Better optics quality
- Baffles to shield mirrors, pipes, vacuum chambers exposed to scattered light
- Photodiodes suspended in vacuum to isolate them from acoustic/seismic noise
- If required, control the position of the benches wrt the interferometer







# Benches under vacuum




First minitower completed in October 2014







Mode cleaner  
lock planned  
Now

# Crucial dates


















Mode cleaner lock yesterday



# Commissioning in detail

- July 2014: early commissioning of IMC
- Oct 2014: first minitower complete, finish commissioning INJ
- Early 2015: all mirrors installed in central building, lock PRMI
- Summer 2015: first end-mirror installed, 1-arm tests
- Fall 2015: full interferometer available, start locking in power-recycled configuration
- Early commissioning of complete interferometer, first science runs
- ??: Install signal-recycling mirror, auxiliary laser system, increase power
- Late commission towards full sensitivity

# Summary

- Advanced Virgo goal: x10 sensitivity wrt Virgo
- Major change in all the Virgo hardware
- Progress in construction – start pre-commissioning
- Now: mode-cleaner locked
- End of construction: fall 2015
- First lock in a power recycled 25 W configuration: end of 2015
- First scientific run with LIGO: 2016
- Increase of sensitivity post-2016, and data takings

